



FOR IMMEDIATE RELEASE

September 22, 2006

Contact:

Melissa Nutt

Director, Business Development

ICON Venue Group

(303) 796-2655

Media Advisory

The Glass is coming: Sprint Center prepares for installation with the placement of 80-foot steel tubes

Sprint Center continues to proceed vertically with the erection of enormous steel tubes that will form the support structure for the glass exterior curtain wall that will form the arena's exterior façade. The tubes are over 80 feet tall and 16 inches in diameter and are being erected on the Grand Blvd. side of the arena site.

On September 21, the tubes arrived from the fabrication shop in St. Louis via I-70 on a semi trailer. They will be erected both vertically and horizontally to form a solid support structure for the curtain wall glass.

The curtain wall glass is set to arrive by ship in Long Beach, CA and make its way, by train, to Kansas City where it will be stored in a warehouse roughly two miles from the arena site. Curtain wall installation is scheduled for early October.

Other Sprint Center construction activities onsite include concrete forming, deck pours, slab on grade concrete work, underground utilities, and architectural and mechanical, engineering, and plumbing (MEP) rough-in activities (studs for interior wall partitions, plumbing and sprinkler piping, ductwork, and electrical conduit).

Photo/Video Opportunity on September 22 and week of September 25 – Media representatives are encouraged to shoot photos/video from the corner of Truman and Grand Blvd.

###